AP2 & Debuncher Aperture

- Goal is to increase acceptance to 40π mm-mrad
- Almost all accelerator components are $> 40\pi$
- Hence, perfect alignment and steering should result in nearly 40π acceptance (except for some known apertures)
- Current measurements
 - -15π mm-mrad for AP2
 - -25π mm-mrad for Debuncher

Improve Aperture


- Alignment
 - Move components
 - Orbit Correction
- Limiting Apertures
 - Modify/fix or replace
- Studies
 - Reverse proton studies and diagnostics
 - Beam Position Measurement Systems

Alignment


- Survey
 - AP1-Target Station-AP2, tunnel settling, etc.
- Motorized stands beam based
- Quadrupole Portable Alignment Fixture
 - Quick/easy for quad move; hope to do a series of moves with beam studies within a shift
- Orbit correction
 - Dipole trims
 - Motorized quad stands

Orbit Correction

- AP2 Trims
 - Few trims; will add more trims
- Debuncher motorized quadrupole stands
 - Real estate limited to add any trims
 - Successful implementation to make bumps
 - 5 motorized stands installed in 2000
 - Will install next set of 10 early in 2002
 - Desire a complete set of local bumps
 - 20 more stands are needed



Local Debuncher 3-Bump



Motorized Quad Stand


zer - Dec Run 2B - AP2 & Debuncher Aperture

2 trims

Apertures

- Determine from lattice/measurements
 - Modify/fix, replace or move
 - Lattice models: being worked upon and verified
- Examples
 - RF cavities move cavities to different locations.
 - Cooling band 4 need/rebuild ?
 - Dipole beam pipes will these be limiting ?
 - Debuncher Injection Region will better steering or larger quad be the answer?

Debuncher Cooling Tanks



Physical Apertures Vert —

Beam Studies

- Majority of studies to be done: 8GeV reverse protons (MI-P1-P2-AP1-AP3-Acc-Deb-AP2)
 - Most reverse proton studies are compatible with an antiproton stack on the accumulator core orbit
 - Forward protons studies have overhead of changing polarity of AP2 and Debuncher
 - Antiprotons from stacking are a small part of *dirty* secondary beam
 - Cannot see antiprotons until end of stacking cycle

Beam Studies-Diagnostics

- AP2 beam line
 - BPMs
 - SEM wire grids
 - Scrapers
- Debuncher
 - BPMs
 - Beam loss monitors
 - Scrapers

BPMs


- AP2 & Debuncher systems old and unreliable; will replace parts of both systems
 - -AP2
 - Prototype sample-hold unit being prepared
 - Will replace DAQ with commercial system
 - Debuncher
 - Specialized receiver for Closed Orbit measurements
 - Will have switching pre-amp, synchronous detector, simple A/D card and a small processor
 - Prototype should be ready early in 2002
- New BPM assembly for target vault (AP2)

Aperture Plan

- Next two years will be mostly alignment; whenever possible:
 - Survey and alignment
 - Installation of trims and motorized quad stands
 - Beam studies and beam based alignment
- Limiting Apertures
 - Studies/investigation
 - Design replacement/modification or plan move
 - Implement


Extra slides

Nice slides to have around




Antiproton Source


End of AP1→Target → Lens → AP2 Start



First Half of AP2


AP-2 INJECTION LINE





Keith Gollwitzer - Dec 12, 2001

Run 2B - A



Keith Gollwitzer - Dec 12, 2001

Run 2B - AP2 & Debuncher Aperture